

SSTS MAINTENANCE REPORT

System Location

Address 1509 15th St N Telephone Number _____
 City Lake Elmo State MN ZIP 55042 Property ID No./GEO Code _____
 Owner Bryce McGrath Pumping Date 11/2/15
Contractor
 Maintainer MEYER SEWER MPCA License No. 915 Telephone Number 651-459-0162

What was done to the system?

Tank(s) Pumped
 Sludge and scum measured.
 Do tanks need to be pumped?
 Yes No (If no provide measurements below)

Report Liquid Capacity in Gallons

Tank 1: 10000 Pumped Tank 2: 10000 Pumped
 Tank 3: _____ Pumped Tank 4: _____ Pumped
 Total Gallons Pumped: 20000

Visual Inspection (note any problems with the system):

NOTE: This does not serve as a compliance inspection

***Tank Measurements-Use Only If Tank(s) Were NOT Pumped**

Tank Length _____ in. Tank Width _____ in. Tank Depth _____ in. = Tank Volume (cubic inches) _____

Tank Radius _____ in. Tank Radius _____ in. 3.14 = Tank Volume (cubic inches) _____


Tank Volume (cu. in.) _____ / 231.01 = Liquid Capacity _____ Gallons / Tank Depth _____ in. = Gallons/Inch _____

Sludge Level _____ in. Gallons Per Inch _____ = Sludge Volume _____ Gallons

Scum Level _____ in. Gallons Per Inch _____ = Scum Volume _____ Gallons

Sludge Volume _____ + Scum Volume _____ = Total Sludge and Scum Volume _____ Gallons

Total Sludge and Scum Volume _____ / Liquid Capacity _____ = Percent Sludge and Scum in Tank _____ %



Tank Depth measured from invert of outlet pipe to bottom of tank

- *Tanks must be pumped if either of the following conditions exist:
1. The top of the sludge layer is less than 12 inches from the bottom of the outlet baffle; or
 2. Total sludge and scum volume is greater than 25 percent of the tank's liquid capacity.