



**WASHINGTON COUNTY, MINNESOTA**  
 Department of Public Health  
 and Environment 651/430-6688

*Scanned 8/1/08*

PERMIT NUMBER

001403010 SEWAGE PERMIT

DRAINFIELD REPLACEMENT PERMIT	205.00
SEPTIC APPLICATION/SOIL REVTRM	195.00
Total Fees :	400.00
Total Paid :	400.00
Total Due :	.00

Owner : PAUL OLSON  
 10300 PERKINS AVE N  
 STILLWATER MN 55062  
 Applicant : JOHN BURLON

*mailed  
5/6/03*

**PERMISSION IS HEREBY GRANTED**

To execute the work specified in this permit on the following described property upon express condition that said persons and their agents, employees and workmen shall conform in all respects to the provisions of the Building Code, and/or Ordinances. This permit may be revoked at any time upon the violation of any of the provisions of said code and ordinances.

Project Address :	10300 PERKINS AVE N	STILLWATER	MN	55062	
Legal Description:	LOT 001 BLOCK 001	ARCOLA HEIGHTS			Geo : 10-030-20-42-0001
Flow Capacity	600 Gal/Day	Tank Volume	2000		
Soil Condition:	Depth to Restriction	90 Inches	Perce Rate	5 Min/Inch	

Soil Treatment Type:  
 Ret. Com Area 384' Back Depth 12'

- Authorized Work / Special Conditions
- Execute proposed alterations to the existing individual sewage treatment system as per approved plans in the area shown on the site plan.
  - Add 1000 gallon tank and 384 square ft drainfield.

\*\* Permit Expiration Date : Sewage Treatment : 2004-05-03

A CERTIFICATE OF OCCUPANCY MUST BE REQUESTED AND ISSUED PRIOR TO USE OR OCCUPANCY OF WORK PERMITTED BY A BUILDING PERMIT.

\*\* This permit shall expire and be null and void if the work authorized by the Building Permit is not commenced within 60 days of the date of issuance or if work is abandoned or suspended for a period of 120 days. Term of the Building Permit is 12 months from date of issue. Term of sewage treatment permit is 12 months from date of issue.

Penalty for violation of any of the provisions of building code: Fine not to exceed five hundred dollars (\$500.00) or imprisonment for not more than ninety (90) days, or both.

Permit Issue Date 2003-05-03 Code Enforcement Officer

*Pleauzel*

# INSPECTION RECORD


BUILDING	DATE	INSP.	COMMENTS
Foundation.....			
Foundation Wall.....			
Plumbing (Groundwork).....			
Heating (Groundwork).....			
Rough Plumbing.....			
Rough Gas Piping.....			
Rough Heating and Ventilation.....			
Framing.....			
Insulation.....			
Fireplace.....			
Chimney.....			
Wallboard or Lath and Plaster.....			
Final Electrical.....			
Final Plumbing.....			
Final Gas Piping.....			
Final Heating and Ventilation.....			
Final Building.....			

SEWAGE TREATMENT SYSTEM	DATE	INSP.	COMMENTS
Installation.....	10-28-03	P. Gurd	Tank Size: <del>2-1000</del> 2-1200 Treatment Area: 762 Ⓟ
As Built.....			Installer: Buelow

DRIVEWAY	DATE	INSP.	COMMENTS
Access.....			
Installation.....			

**NOTES:**

*Chambers*



• 50' Boring Test Holes

⊙ Percolation Test Holes


+ Well

300'

465'

465'

270' Perkin Ave N.





# STANDARD SYSTEM DESIGN INDIVIDUAL SEWAGE TREATMENT SYSTEM

WASHINGTON COUNTY HEALTH, ENVIRONMENT & LAND MANAGEMENT  
14900 N. 61ST STREET, P.O. BOX 3803, STILLWATER, MN 55082-3803  
612/430-6708 OR 612/430-6656 FAX 612/430-6730

Owner's Name
Job Site Address <u>10300 PERKINS AVENUE</u>
City or Township <u>STILLWATER TOWNSHIP</u>
Use of Building

Design Flow Rate <u>600 GPD</u>	Land Slope <u>1% OR LESS</u> Percent
Required Tank Sizes <u>1200</u> Gallons	and <u>MINIMUM 1000</u> Gallons
Type of System (standard, at grade or bed) <u>STD - UPGRADE</u>	
System Size: <u>762</u> TOTAL Square Feet	Lineal Feet <u>36"</u> Trench Width
Depth of rock below pipe <u>12"</u>	Depth of Rock Above Pipe <u>2</u>
MINIMUM Depth of Trench From Existing Grade <u>6"</u> Inches	MAXIMUM <sup>COVER</sup> Depth of Trench From Existing Grade <u>24"</u> Inches
Recommended Number of Trenches <u>ADD 1 TRENCH</u>	Recommended Length of Trenches <u>128</u> LIN FT
Trench Spacing Measured Center to Center Feet	
Any Other Special Conditions <u>ADD BEDROOM - UPGRADE</u> <u>760 NEEDED/376 PRESENT = 384 ADD = 128 LIN FT AT 36" W</u> <u>PERC RATE TO 1.27 UP FROM ORIGINAL .83 -</u>	

IF PRESSURE DISTRIBUTION IS USED, COMPLETE THE PRESSURE DISTRIBUTION WORK SHEET ATTACHED.

This design must be accompanied by a site plan that clearly shows the location of the area tested and approved by the following:

1. Use an appropriate scale and indicate direction by use of a north arrow.
2. Show ALL property boundaries, rights-of-way, easements, wetlands. If necessary, an enlarged detail of the house site may also be required.
3. Show location of house, garage, driveway and all other improvements existing or proposed.
4. Show location and layout of sewage treatment system.
5. Show location of water supply (well and/or community supply line).
6. Dimension all setbacks and separation distances.

This system has been designed by a Pollution Control Agency (PCA) Certified Professional.

Designer Name <u>ORIN KOELKERITZ</u>	PCA Certification # <u>1044</u>
Address <u>1118 NEAL AVE S AFTON MN</u>	Phone # <u>651-436-8820</u>
Signature <u>[Signature]</u>	Date <u>4-16-03</u>

An Equal Employment Opportunity/Affirmative Action Employer  
If You Need Assistance Due to Disability or Language Barrier, Please Call 430-6656 OR 430-6708 (TDD 439-3220)

436 2100

# INDIVIDUAL SEWAGE TREATMENT SYSTEM WORKSHEET

- A. Estimated 600 FLOW  
measured \_\_\_\_\_ gpd  
 $\text{measured} \times 1.5 = \text{estimated}$  gpd
- B. 1200 + New SEPTIC TANK VOLUME  
gallons - *MINIMUM 1000*
- C. SOILS (Site evaluation data)  
Depth to restricting layer = \_\_\_\_\_ feet
- D. Maximum depth of system C - 3 ft = \_\_\_\_\_ feet
- E. Percolation rate 5 MPI - *6-15 - 1.0 pm/5 min*
- F. Soil Sizing Factor 1.27 sq ft/gpd (See table 3)

Number of Bedrooms	Type I	Type II	Type III	Type IV
2	300	225	180	
3	450	300	218	
4	600	375	256	60% of the values in Type I, II or III columns
5	750	450	294	
6	900	525	332	
7	1050	600	370	
8	1200	675	408	

- H. TRENCH BOTTOM AREA  
For trenches with 6 inches of rock below the pipe:  
 $A \times F = 600 \times 1.27 = 762$  sq ft of bottom area
- I. For trenches with 12 inches of rock below the pipe:  
 $A \times F \times 0.8 = \text{ } \times \text{ } \times 0.8 = \text{ } \text{ sq ft of bottom area}$
- J. For trenches with 18 inches of rock below the pipe:  
 $A \times F \times 0.66 = \text{ } \times \text{ } \times 0.66 = \text{ } \text{ sq ft of bottom area}$
- K. For trenches with 24 inches of rock below the pipe:  
 $A \times F \times 0.6 = \text{ } \times \text{ } \times 0.6 = \text{ } \text{ sq ft of bottom area}$
- L. BED BOTTOM AREA  
For seepage beds with 6 or 12 inches of rock below the pipe;  
 $1.5 \times A \times F = 1.5 \times \text{ } \times \text{ } = \text{ } \text{ sq ft of bottom area}$

Number of Bedrooms	Minimum Liquid Capacity	Liquid capacity with garbage disposal
2 or less	750	1125
3 or 4	1000	1500
4 or 6	1500	2250
7, 8 or 9	2000	3000
over 9		.....

*AND 2ND TANK OF MINIMUM 1000 GAL*

- M. ROCK VOLUME IN CU FT  
Rock depth below distribution pipe plus 0.5 foot times bottom area:  
 $M = \text{Rock depth (ft) + 6 inches} \times \text{Area (H, I, J, L or K)}$   
 $(\text{ } \text{ ft} + 0.5 \text{ ft}) \times \text{ } = \text{ } \text{ cu ft}$
- N. ROCK VOLUME IN CU YDS  
Volume in cu ft divided by 27  
 $M + 27 = \text{cu yds } \text{ } + 27 = \text{ } \text{ cu yds}$
- O. ROCK WEIGHT  
Cubic yards times 1.4 = tons  
 $N \times 1.4 = \text{tons } \text{ } \times 1.4 = \text{ } \text{ tons}$


Soil Characteristics and Required Areas for Sewage Treatment

Percolation Rate in Minutes per Inch (MPI)	Soil Texture	Square feet per gallon per day	Gallons per day per square foot
Faster than 0.1 *	Coarse Sand	.....	.....
0.1 to 5	Sand	0.83	1.20
0.1 to 5	Fine sand **	1.67	0.60
6 to 15	Sandy Loam	1.27	0.79
16 to 30	Loam	1.67	0.60
31 to 45	Silt Loam	2.00	0.50
46 to 60	Clay Loam	2.20	0.45
Slower than 60 ***	Clay	.....	.....

- DISTRIBUTION  
(Check one based on slope)  
 Bed (less than 6% slope)  
 Trenches  
 Drop boxes (any slope)  
 Distribution box (level to slightly sloping)

- TRENCH LENGTH  
P. Select trench width = 3 ft  
Q. Divide bottom area by trench width: (H, I, J, or K) + P = lineal feet  
 $\text{ } + \text{ } = \text{ } \text{ lineal feet}$

- LAWN AREA  
R. Select trench spacing, center to center = \_\_\_\_\_ feet  
S. Multiply trench spacing by lineal feet  $R \times Q = \text{sq ft of lawn area}$   
 $\text{ } \times \text{ } = \text{ } \text{ sq ft}$



## LAYOUT (Use other side)

1. Select an appropriate scale; one square = \_\_\_\_\_ feet.
2. Show pertinent property boundaries, right-of-way, easements.
3. Show location of house, garage, driveway, and all other improvements, existing or proposed
4. Show location and layout of sewage treatment system.
5. Show location of water supply well.
6. Dimension all set backs and separation distances.



# SITE REVIEW and/or SEPTIC PERMIT APPLICATION

## Washington County Public Health & Environment

14949 62nd Street N, PO Box 3803  
Stillwater, MN 55082-3803  
651/430-6688 FAX 651/430-6730

Paid \$ 400.

Receipt # 45082

### Make checks payable to WASHINGTON COUNTY

- \$190 - New Home Drainfield
- \$ 85 - Replace Existing System with a Drainfield System
- \$315 - New Home Mound
- \$210 - Replace Existing System with a Mound System
- \$315 - Alternative/Experimental System
- \$185 - Individual Lot
- \$130 - Subdivision Soil/Site Review - Base fee Plus \$55/lot
- \$ 25 - Additional Review Fee (1 hour minimum)
- \$ 30 - Renewal of Previous Permit Fee

0014-03010

*Mail to John*

Legal Description and Parcel Identification Number (especially if this is for a NEW SUBDIVISION OR MINOR SUBDIVISION)

Applicant Address 10300 Perkins City State Zip Phone

Owner (if different from applicant) Paul Olson Address City State Zip Phone

New Home  Existing Home  New Business  Existing Business  Number Of Bedrooms: 4 Gallons Per Day: 600

Check the following fixture(s) which are or will be installed: Garbage Disposal NO Recreational Bathing Facility: (jacuzzi, hot tub, etc.) NO

New Home  Drainfield System  Mound System  Alternate/Experimental System  Existing Permit Renewal

Existing Home Replacement System  Drainfield System  Mound System  Tank Replacement Only

Site Approval Only  If this site has been previously approved, attach copy of approval letter Additional Soil Test Data for Previously Approved Site

The following exhibits are required as part of this application and shall be attached hereto: Percolation Test Reports; Soil Boring Logs; Site Plan drawn to scale showing location of buildings, lot lines, percolation test holes, soil boring holes, proposed location of system and well; one (1) copy of the System Design; and one (1) copy of the Final Building Plan. The house and the drainfield areas must be staked. Inaccurate or incomplete information will result in delays in processing.

**AGREEMENT:** The undersigned hereby makes Application for Permit to Install or Extend Sewage Treatment System herein specified, agreeing that all such work shall be done in strict accordance with ordinances and regulations of the County of Washington, Minnesota. Applicant agrees that the Site Plan, Sketches and Design submitted herewith, and which are reviewed by Washington County, together with any requirement and/or restriction made necessary by conditions peculiar to a particular location, shall become a part of the permit. Applicant further agrees to provide access, at reasonable times, to Washington County for the purpose of performing inspections required and that no part of the system shall be covered until it has been inspected and accepted. **APPLICATION IS FOR AN INSTALLATION AT A SPECIFIC LOCATION; ANY DEVIATION FROM THE APPROVED LOCATION WILL VOID THE PERMIT.** It shall be the responsibility of the applicant for the permit to notify the Office of the Washington County Dept. of Public Health & Environment that the installation is ready for inspection.

I hereby certify the above to be true and correct. In connection with your request for a soil review/septic permit, I hereby give Washington County Department of Public Health and Environment permission to enter upon my property during normal business hours for the purpose of determining the suitability of the location, design, and construction, which may include minor excavation or soil borings by the Department.

Signature of Applicant (Owner or Contractor)

Date

### THE AREA BELOW IS FOR COUNTY USE ONLY

SITE EVALUATION: BY INSPECTOR P. G. ... DATE 4-22-03

SETBACKS:	REQUIRED (CIRCLE APPROPRIATE ITEM(S))					ACTUAL
	50'	75'	100'	150'		
Well (including adjacent property)						
Wetland, Pond, Lake, Stream, River, or Bluffline						

CONCLUSIONS: Site Suitable:  Site Unsuitable:  Additional Tests Required:  Verify Use: \_\_\_\_\_ Bedrooms

NOTES: Lot Size \_\_\_\_\_ Year Built \_\_\_\_\_  
10030 20420004 no site plan

3-4 BR

~~439-8381~~

Permit Fee \$ 25

OFFICE OF THE ZONING ADMINISTRATOR  
WASHINGTON COUNTY, MINNESOTA  
Tel. 439-3220

PERMIT TO INSTALL SEWAGE DISPOSAL SYSTEM

Owner PAUL E OLSON Permit No. 1765  
NAME STILLWATER  
10300 PERKINS AVE NO, ARCOLA HETS TWP  
ADDRESS

MINIMUM SYSTEM REQUIRED: 3 Bedrooms, Percolation Rate 5 M in/Inch

Septic Tank 1200 Gal. Liquid Capacity Lift Station \_\_\_\_\_ Gal.

Distribution Box \_\_\_\_\_ Drop Box concrete with removable cover

Absorption Trench - Square Feet 375 Lineal Feet 188 Width 24"

Depth of Rock Below Tile Lines 12 Inches, Above Tile 2 Inches

Depth of Trench - Minimum Cover 18 Inches, Maximum Cover 36 Inches

Minimum Number of Lines 2 Maximum Length of Individual Line 100 Ft.

Recommended Number of Lines 2 at 94'

Minimum Spacing of Lines 6 1/2 Ft. Center to Center.

*Inspection of Installation Must Be Accomplished By This Office Before Any Portion of System Is Covered.*

Special Conditions system must go in area tested and shown on attached site plan. Line from house to tank must be cast iron.

System Inspected \_\_\_\_\_ DATE

Installation Approved \_\_\_\_\_ INSPECTOR

Comments \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**PERMIT:** Permission is hereby granted to the above named applicant to perform the work described in the application, to the specifications shown under minimum system required. This permit is granted upon express condition that the person to whom it is granted, and his agents, employees and workmen shall conform in all respects to ordinances of Washington County, Minnesota. This permit may be revoked at any time upon violation of any said ordinance, and permit shall be void if work is not commenced within (6) months. Installer must hold current Septic Installer License with Washington County.

Approved: Al Goodman 2-9-78  
(ZONING ADMINISTRATOR) (DATE)

OFFICE OF THE ZONING ADMINISTRATOR  
WASHINGTON COUNTY, MINNESOTA  
Tel. 439-3220

Permit Fee \$ \_\_\_\_\_

PERMIT TO INSTALL SEWAGE DISPOSAL SYSTEM

Owner PAUL I. OLSON

Permit No. 1765

10300 PERKINS AVE. N.W.  
NAME

MINIMUM SYSTEM REQUIRED: 3 Bedrooms, Percolation Rate 5 M In/Inch  
ADDRESS

Septic Tank 1200 Gal. Liquid Capacity Lift Station \_\_\_\_\_ Gal.

Distribution Box \_\_\_\_\_ Drop Box \_\_\_\_\_

Absorption Trench -- Square Feet 375 Linear Feet 188 Width 24

Depth of Rock Below Tile Lines 12 Inches, Above Tile 2 Inches

Depth of Trench -- Minimum Cover 12 Inches, Maximum Cover 36 Inches

Minimum Number of Lines 2 Maximum Length of Individual Line 100 Ft.

Recommended Number of Lines 2 or 94'

Minimum Spacing of Lines 6 1/2 Ft. Center to Center.

*Inspection of Installation Must Be Accomplished By This Office Before Any Portion of System Is Covered.*

Special Conditions Septic tank is to be installed in area shown on attached site plan. Line from house to tank must be covered.

System Inspected 8-16-78  
DATE

Installation Approved Russ Anderson  
INSPECTOR

Comments \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

PERMIT: Permission is hereby granted to the above named applicant to perform the work described in the application, to the specifications shown under minimum system required. This permit is granted upon express condition that the person to whom it is granted, and his agents, employees and workmen shall conform in all respects to ordinances of Washington County, Minnesota. This permit may be revoked at any time upon violation of any said ordinance, and permit shall be void if work is not commenced within (6) months. Installer must hold current Septic Installer License with Washington County.

Approved: [Signature] 2-9-78  
ZONING ADMINISTRATOR (DATE)




-SOIL BORINGS-

Soil borings are made in order to determine the type and structure of soils at various depths as well as the location of the water table, impervious strata or bedrock.

Borings are most easily made with a hand auger, however other expedients may be utilized - back hoe, post hole auger, etc.

Soils encountered at various depths should be listed as to appearance, texture and composition.

Depth at which water, bedrock or heavy clay layer is encountered should be recorded.



## LOG OF SOIL BORINGS

BORING NO. 1		BORING NO. 2		BORING NO. 3		BORING NO. 4	
DEPTH IN FEET	SOIL DESCRIPTION	DEPTH IN FEET	SOIL DESCRIPTION	DEPTH IN FEET	SOIL DESCRIPTION	DEPTH IN FEET	SOIL DESCRIPTION
0	top soil	0	top soil	0	top soil	0	top soil
1/2		1/2		1/2	sand	1/2	
1		1	sand	1		1	
1 1/2	sandy loam (heavy)	1 1/2		1 1/2		1 1/2	
2		2		2		2	
2 1/2		2 1/2	sandy loam (heavy)	2 1/2		2 1/2	sandy loam (heavy)
3	sand	3		3		3	
3 1/2		3 1/2		3 1/2		3 1/2	
4		4	sand	4		4	
4 1/2		4 1/2		4 1/2		4 1/2	
5		5		5		5	
5 1/2		5 1/2		5 1/2		5 1/2	
6		6		6		6	sand
6 1/2		6 1/2		6 1/2		6 1/2	
7		7		7		7	
7 1/2		7 1/2		7 1/2		7 1/2	
8		8		8		8	
8 1/2		8 1/2		8 1/2		8 1/2	
9		9		9		9	

PERCOLATION TEST DATA SHEET

Test hole location (see attached diagram) Hole number 11  
 Date test hole was prepared 1-7-78, Depth of hole bottom, 3.5 inches.  
 Diameter of hole, 6 inches.

Soil data from test hole:

Depth, inches	Soil texture
<u>33</u>	<u>Sand</u>

Method of scratching sidewall \_\_\_\_\_

Depth of pea-sized gravel in bottom of hole, 2 inches.

Date and hour of initial water filling 1-7-78 5:40pm

Depth of initial water filling, (to test to normal) inches above hole bottom.

Method used to maintain at least 12 inches of water depth in hole for at least 4 hours We poured about 3 buckets of water in at 5:40 pm - it drained

Percolation test readings made by Paul & Hope Olson on 1-8-78 starting at 8 a.m. Maximum water depth above gravel 29 inches during test, 6 inches. about 4" every 1 1/4 min.

Time	Time Interval, Minutes	Measurement, inches	Drop in water level, inches	Remarks
12:35:00	—	31 3/4	—	Hole filled - found empty
12:37:00	2 min	30 1/2	4 1/4"	Hole emptied shortly.
1:21:40	—	30 1/4	—	Hole filled - found empty
1:25:40	3 min	35	4 3/4	Hole emptied shortly
1:32	—	27 1/2	—	Hole filled - found empty
1:56	4 min	34 1/4	6 1/4	Hole emptied shortly
2:18:15	—	28 3/4	—	Hole filled
2:21:45	3 1/2	32 1/4	5 1/2	Hole emptied shortly
2:59	—	27 1/8	—	Hole filled
3:03	4 min	32 7/8	2 1/2	Hole emptied shortly.

PERCOLATION TEST DATA SHEET

Test hole location (see attached diagram) Hole number I  
 Date test hole was prepared 1-7-78, Depth of hole bottom, 34 inches.  
 Diameter of hole, 6 inches.  
 Soil data from test hole:

Depth, inches	Soil texture
<u>34</u>	<u>Sandy loam - 1st 2 feet;</u>
	<u>then sand</u>

Method of scratching sidewall A stick with several nails driven in.

Depth of pea-sized gravel in bottom of hole, 2 inches.

Date and hour of initial water filling 1-7-78 5:40 pm

Depth of initial water filling, (too fast to measure) inches above hole bottom.

Method used to maintain at least 12 inches of water depth in hole for at least 4 hours We poured about 3 buckets of water in at 5:40 -- it drained out immediately at a rate of about 4" every 2 min.


Percolation test readings made by Paul & Hope Olson on 1-8-78 starting at 6:10 p.m. Maximum water depth above gravel during test, 6 inches.

Time	Time Interval, Minutes	Measurement, inches	Drop in water level, inches	Remarks
12:40'45"	-	31 1/4	-	Hole filled with 1 bucket of water
12:42'30"	1 min 45 sec	36 3/4	5 1/2"	Hole emptied rapidly
1:25'15"	-	31 1/2	-	Hole filled with 1 bucket of water
1:30'00"	1 min 45 sec	36	4 1/2"	Hole emptied rapidly
1:32'15"	-	32 1/4	-	Hole filled with a bucket of water
1:33'45"	1 min 30 sec	35	2 3/4"	Hole emptied rapidly
1:56'45"	-	30 5/8	-	Same as above
1:58'30"	1 min 15 sec	34 5/8	3 3/4"	" "
2:14'45"	-	30 3/4	-	" "
2:16'45"	2 min	35 1/2	1 1/4"	" "
3:04'20"	-	29 1/4	-	" "
3:06'20"	2 min	31 1/8	1 7/8"	" "

\* Sandy soil caved in when water was added first few times!



# AS-BUILT REPORT INDIVIDUAL SEWAGE TREATMENT SYSTEM



**Washington County Public Health and Environment**  
14949 62<sup>nd</sup> Street North, PO Box 3803, Stillwater, MN 55082-3803  
651/430-6655 FAX 651/430-6730

Legal Description or Complete Street Address of Septic System Installed			City or Township	
Owner Name	Mail Address	City	State	Zip
PAUL + HOPE OLSON 18300 PERKINS AVE N STILLWATER TOWNSHIP				
Installer	Mail Address	City	State	Zip
BUELOW EXC 13254 2074 ST N STILLWATER MN 55082				
Septic Tank Information				
Tank Manufacturer:		Liquid Capacity:		
PLASTED		1500		

PUMP CHAMBER (if installed)			
Tank Manufacturer:	Liquid Capacity:	Horsepower of Pump:	Type of Warning Device:
Pump Discharge in Gallons Per Minute:		at	Feet of Head
		Number of Gallons Pumped Per Cycle:	

DRAINFIELD TRENCH SYSTEM		BED OR MOUND SYSTEM		
Width:	Length of Each Trench:	Rock Bed Length:	Width:	Area:
36"	VARIES			
Depth of Trench Bottom from Finished Grade:		Bed Depth from Grade:		
6-24"				
Method of Distribution:		MOUND:		
<input type="checkbox"/> Pressure <input type="checkbox"/> Distribution Box <input checked="" type="checkbox"/> Drop Box		Upslope Sand Base Depth:                      Downslope Sand Base Depth:		
Depth of Rock Under Distribution Pipe:		Depth of Rock Under Pipe:		
12"				
Square Footage of Tested Area Used:		PRESSURE DISTRIBUTION SYSTEM		
820		Lateral Inside Diameter:	Length:	Perforation Size:
Trench Bottom Square Footage Required:	Area As Built:	Spacing:	Number:	Perforation Spacing:
384				

Complete site plan on attached sheet. On the site plan, include location of the following items:  
Structures, septic tank, pump chamber, line from house to tank treatment system, distribution lines, distribution or drop boxes, well, and driveway. Show all distances applicable to the sewage treatment system (distance from structure to tank, tank to treatment system, distance between distribution lines, length of distribution lines, and distance between well and sewage treatment system). Indicate NORTH on the site plan and the scale of the plan.

I hereby certify that the system at the above referenced address was installed according to the Washington County Individual Sewage Treatment System Ordinance requirements.

Signed: [Signature] MPCA License # 389 Dated: 10-03

WASHINGTON COUNTY SEPTIC PERMIT NUMBER: 001403010      INSTALLED DATE: 10-03

